### Memo

Title	Application for Minor Ancillary Facility – Cope Street Waterloo			
Date	07 September 2021			
Doc Number	SMCSWSWL-JHG-SWL-EM-MEM-000001			
То	George Kollias (Environmental Representative), Larry Clark (Acoustic Advisor)			
From	Julian Paul (JH Environment & Sustainability Advisor)			

#### 1.1 Introduction

This application relates to the minor ancillary facility associated with Waterloo ISD proposed on Cope Street, adjacent to the Waterloo ISD Construction Site. The minor ancillary facility is required to provide necessary lunch shed, office and first aid facilities for utilities subcontractors to adhere to the COVID-19 workplace restrictions (e.g. 1 person per 4m²) and separate work crews on the Waterloo ISD.

This minor ancillary facility will comprise of two caravan trailer lunch sheds, one storage container for office use & one storage container for first aid use, parked tandem along Cope Street. The proposed minor ancillary facility is in addition to those approved under the EIS. A minor ancillary facility application form is located in Annexure A, in accordance with Condition of Approval (CoA) A18.

### 1.2. Compliance with CoA A18

One approval pathway for minor ancillary facilities is identified in the Planning Approval:

 Minor ancillary facilities not identified in the EIS. Minor ancillary facilities would be of minimal environmental impact and may be approved by the Environmental Representative (ER) in accordance with CoA A18.

This minor ancillary facility adjacent to the Waterloo ISD Construction Site is not identified as an ancillary facility in the EIS. The minor ancillary facility is located within the revised Waterloo Station Construction site included in the Sydney Metro Chatswood to Sydenham Submissions and Preferred Infrastructure Report (SPIR). Therefore, if approved by the ER, the Cope Street minor ancillary facility can be established where it satisfies the criteria of CoA A18.

Table 1 Compliance requirements of CoA A18

CoA	Requirement	Compliance		
Minor ancillary facilities comprising lunch sheds, office sheds, and portable toilet facilities, or the like, that are not identified in the EIS as amended by the documents listed in A1 and which do not satisfy the criteria set out in Condition A16 of this approval must satisfy the following criteria:		This memo and an Application for Minor Ancillary Facility (Annexure A) has been prepared and provided to the ER to allow the assessment of the impacts of the proposed minor ancillary facility comprised of two caravan trailer lunch sheds, one site office & one first aid shed.		
A18 a)	(a) have no greater environmental and amenity impacts than those that can be managed through the implementation of environmental measures detailed in the CEMP required under Condition C1 of this approval; and	This memo and an Application for Minor Ancillary Facility (Annexure A) has been prepared and provided to the AA and ER to review the noise impacts of the proposed minor construction ancillary facility.		

A18 b)	I recidences and hijeinesses, after consideration of	There will be minimal environmental impact with respect to surrounding residences and businesses, in relation to noise, traffic and access impacts, dust and odour and visual impacts as described in Annexure A.
	(b) have been assessed by the ER to have: ii. minimal environmental impact with respect to waste management and flooding; and	There will be minimal environmental impact with respect to waste management and flooding as described in Annexure A.
	(b) have been assessed by the ER to have: iii. no impacts on biodiversity, soil and water, and heritage items beyond those already approved under other terms of this approval.	There will be no environmental impact with respect to biodiversity, soil and water, and heritage as described in Annexure A.

# Annexure A Application for Minor Construction Ancillary Facility

, ,		Cope Street, Waterloo, NSW, 2017
		Refer to site location plan on page 7.
Date works to commence:		Date works to finish:
31st August 2021		May 2022
		ordance with A18 (select all that apply):
Lunch sheds	X	
Office sheds	X	
Portable toilet facilities	X	

#### Step 2 - Environment and Sustainability Manager (or delegate) review

Can the environmental and amenity impacts associated with the proposed minor ancillary facility be managed through the implementation of environmental measures detailed in the CEMP?

The minor ancillary facility will be located on Cope Street, adjacent to the Waterloo ISD construction site. Mitigation and management measures to be implemented for these works have been identified in the sub-plans and procedures in the CEMP (see Section 6.1), approved by the Secretary on 31/07/2020. These mitigation measures will also be incorporated into an ECM for the ancillary facility.

There are no other additional environmental and amenity impacts than those that can be managed through the implementation of environmental measures detailed in the CEMP, approved by the Secretary on 31/07/2020.

Is the proposed minor ancillary facility within the Project boundary?

The minor ancillary facility is located within the revised Waterloo Station Construction site included in the Sydney Metro Chatswood to Sydenham Submissions and Preferred Infrastructure Report (SPIR).

Is the ancillary facility included in the EIS?

No. The minor ancillary facility was not assessed as part of the EIS.

Provide a brief discussion regarding the following environmental issues associated with the proposed minor ancillary facility:

 compliance with the Interim Construction Noise Guidelines (DECC, 2009) The new ancillary facility will be in compliance with this guideline. The proposed facilities are located approximately 20 metres away from residential receivers along Cope Street. The two caravans and site office will be powered by 5 kVa diesel generators, which will have a minimal impact upon the residential receivers. The generator will be required to be on 24/7 to power the refrigerators. The site office generator will only be used during the day period until the sound power level can be confirmed.

The noise impact from the new amenity facilities have been assessed through the Sydney Metro Out of Hours Work Application Form model, refer to Table 2 and Table 3. The caravan contains an enclosure for the diesel generator at the rear of the facility, which is predicted to achieve a 25 dB noise reduction, according to the Sydney Metro Out of Hours Work Application Form model.

Based on these results it is expected that the noise impact will be below NML during the standard & evening period with a 1 dB exceedance during the night period. These impacts will be verified by attended noise monitoring for compliance with the predicted noise level.

It is noted the first aid shed will not require power and hence will not cause any additional impacts to the receivers identified above.

	<ul> <li>Environment and Sustainability M</li> </ul>	
•	traffic and access impacts (in accordance with CoA E57)	Traffic on Cope Street will not be affected by the minor ancillary facility as it will be parked in allocated car spaces, leased from Council through a stand plant permit (or the like). The components that form the minor ancillary facility will follow road rules and adhere to the Construction Traffic Management Plan.  As assessed in the SPIR, the impact as a result of a loss of on-street parkin is expected to have a minimal impact as there is alternative long term residential on-street parking on adjacent streets. The community consultation team will notify the residents on Cope Street of the change to parking.
•	dust and odour impacts	The facility is to be established on road pavement (hardstand). Dust is not expected to present an issue. Odour will be managed through regular waste management of the facility.
•	visual (including light spill) impacts	The single stack caravan sheds and storage containers will be situated on top of hardstand in leased car spaces to minimise the visual impact to the surrounding vicinity. Additionally, the facilities will not directly overlook adjoining private open spaces of residential properties.  Lighting will be orientated away from residential receivers where possible. No overshadowing on residential receivers would occur due to the distance between the facilities and nearest residential receivers (located on Cope Street).  Lighting will be adjusted to minimise any potential impact and installed consistent with the mitigations in the Visual Amenity Management Subplan (See Section 7.2).
•	waste management	All general waste such as office waste will be removed via a licenced contractor overseen by JH and will be managed in accordance with the Waterloo ISD Waste & Recycling Procedure.
•	flooding	Flooding impacts will be unchanged the same due to the caravans being elevated on hardstand and the office and first aid container taking up a small footprint. Stormwater drains will remain unobstructed by the facilities.
•	biodiversity	The facility is to be installed on established land. There will be no vegetation clearing/impacts to biodiversity as a result of the additional ancillary facility. No additional assessment will be required.
•	soil and water	The facility is to be installed on established land and the waste water will be captured in a septic tank and disposed of by a licenced contractor overseer by JH. There will be no impacts to soil or water systems as a result of the additional ancillary facility. No additional assessment will be required.
•	heritage items	There will be no impacts to heritage items as a result of the additional ancillary facility. No additional assessment will be required.

# **Sydney Metro Out of Hours Work Application Form Extract**

**Table 1: Predicted Noise Level Aspects** 


Noise Aspect	Select the most applicable value for each noise aspect below and enter into Table 2.				
	Impact sheet piling rig				
	Hand-held tamper, excavator with hammer, rock-breaker, driven / vibratory piling, concrete saw, diamond saw, air track drill, large dozer, hand-held rail grinder	95			
1. Plant / Equipment Noise	<u>Jackhammer</u> , rock crusher, angle grinder, pneumatic hammer, medium dozer, tracked loader, impact wrench	90			
Level at 10m Including non- continuous use reduction (-5dBA)	Mainline tamper, ballast regulator, dynamic track stabiliser, vibratory roller, mainline rail grinder, ballast train (pour / fill ballast), chainsaw, tub grinder / large mulcher, scraper, grader, super-sucker / vacuum truck, large backhoe / wheeled front-end loader, bored piling, pavement profiler, fixed crane, tracked excavator				
and annoying activity penalty (+5dBA) for as per ICNG (refer to ICNG Appendix B for predicted noise	Small bulldozer, small excavator, tower crane, truck-mounted crane, forklift, bobcat, skid-steer front-end loader, road truck / truck and dog, dump truck, concrete truck / pump / mixer, compressor, non-vibratory / large pad foot roller, whacker packer / compactor, water cart, pavement laying machine, asphalt truck and sprayer, line marking truck, standard penetration testing, welder, pin puller	80			
Underline indicates vibratory generating	Concrete vibrator, cherry-picker scissor lift / elevated work platform / Franna crane, small backhoe, front end loader, fence post driver, electric drill rig, hand held rattle gun, generator (diese / petrol), spreader	<mark>75</mark>			
plant / equipment	Lighting tower, medium-rigid truck / semi-trailer, welding equipment, tracked excavator, small front end loader				
	Light vehicle, hand-tools (no impact), small cement mixer, attenuated generator (inside housing), tracked excavator	65			
2. Multiple Plant	More than one of the noisiest plant being used simultaneously at roughly the same location	+5			
	Existing screening between site and receiver (buildings, cuttings, canopies, etc.)	- 5			
3. Local Screening	Temporary screening to be implemented near work site	- 10			
	Acoustic shed or enclosure	<mark>- 25</mark>			
	< 10 metres	0			
	10 to 20 metres	- 5			
	20 to 35 metres	<mark>- 10</mark>			
4. Distance	35 to 60 metres	- 15			
Attenuation	60 to 100 metres	- 20			
	100 to 180 metres	- 25			
	180 to 350 metres	- 30			
	350 to 1,000 metres	- 40			

Table 2: Predicted Noise Levels and Exceedances of RBLs and/or NMLs (dBA)

Skip this section if Section 3 has been completed in full.										
	Noisiest Plant /	Dansiyar Type	Sydn A Table	ey Metro O application f 1, then add	licable valu ut of Hours Form Extrad I to determi Noise Level	Work ct ne the	Level (1 + 2 +		es)	
Period (only complete as applicable for each period)	Equipment (state the noisiest plant / equipment to be used during each applicable OOH period)	Receiver Type (state 'Res' or 'Non-Res' as applicable for closest receiver to noisiest plant / equipment)	1. Plant / Equipment Noise Level	2. Multiple Plant / Equipment	3. Local Screening	4. Distance Attenuation	Predicted Noise 3+4)	RBL (for Res)	NML (for Non-Re	Exceedance (Predicted Noise Level minus RBL for Res or NML for Non-Res)
Daytime OOH *	attenuated generator (inside housing)	Res	75	5	-10	-10	60	54	64	Below NML
Evening OOH *	attenuated generator (inside housing)	Res	75	5	-25	-10	45	47	52	Below NML
Night Time OOH *	attenuated generator (inside housing)	Res	75	5	-25	-10	45	39	44	+1 dB

<sup>\*</sup> Refer to OOH period timings under Section 2 of the Sydney Metro OOHW Permit Form.

## **Location Map**



Step 3 – Internal sign off						
Project Director						
Name:	Signature:	Date:				
Andrew Knispel	f. hiful	07/09/2021				
Environment and Sustainability Manager						
Name:	Signature:	Date:				
Sally Reynolds	S.Reynolds	07/09/2021				

Step 4 – Environmental Representative sign off					
In conjunction with the AA, have ancillary facility?	Υ				
Does the proposed minor ancillar	Y				
Name:  George Kollias  Signature:  Globlias		Date: 08/09/21			

#### Additional comments / notes:

#### Condition 1:

Generators in-built to caravans may be used during OOH periods as per the included noise assessment. The Contractor is to provide details on the verified noise levels and noise assessment for the 5kVa generator proposed for the site sheds, before use during any OOH period (excluding for a trial if this can only be done during an OOH period). The noise assessment must consider the inclusion of appropriate barrier reduction where the generator is not within an enclosure, and cumulative noise with generator assessed for the caravans. These conditions must be fulfilled to the satisfaction of Sydney Metro, Acoustics Advisor and the Environmental Representative.